



## **2023 Annual Wastewater Performance Report**

Manager of Public Works, David Armstrong  
Superintendent of Water and Wastewater Utilities, Don Richards

January 30, 2024



## EXECUTIVE SUMMARY

The Corporation of the Town of Gananoque's Public Utilities Division is pleased to provide the 2023 Annual Wastewater Performance Report. The purpose of this report is to keep the public and Council informed regarding the quality of the Town's Wastewater Treatment and Collection System.

The employees of the Town of Gananoque are committed to and share in the responsibilities for implementing, maintaining, and contributing to the continual improvement of the wastewater system.

This Annual Wastewater Performance Report is prepared in accordance with the Certificate of Approval # 0999-7X8QL3. Included with this report is the analytical data, plant flows, process flow schematic and the overall performance of parameter removals.

---

David Armstrong  
Manager of Public Works

---

Don Richards  
Water and Wastewater Utilities Superintendent



## TABLE OF CONTENTS

	Page #
Executive Summary	1
Table of Contents	2
List of Acronyms & Definitions	3
1. Introduction	4
2. Facility Description	4
3. Monitoring Raw Influent and Treated Effluent Data	4
3.1 Influent and Effluent Lab Results, Limits and Objectives	4
Table 1: Raw Influent Results	4
Table 2: Effluent CBOD5 and Total Suspended Solids	5
Table 3: Effluent Total Phosphorous	5
Table 4: Effluent pH	5
Table 5: Effluent E. Coli	7
3.3 Flow Data	7
Table 6: Average Monthly Flows	7
3.2 Bypasses and Overflows	7
Table 7: 2023 Bypass and Overflow Events	8
4. Operating Challenges and Corrective Action	8
4.1 Maintenance on Major Structures and Equipment	8
4.2 Effluent Quality Assurances/Control Measures	8
5. Calibrations/Maintenance of Effluent Monitoring Equipment	9
6. Key Contacts	9

## APPENDICES

Appendix A:	Process Flow Schematic
Appendix B:	Summary Performance Report
Appendix C:	Bishop Water Biosolids Final Report
Appendix D:	Summary of Capital Projects

## **LIST OF ACRONYMS & DEFINITIONS**

Annual Average Concentration	The arithmetic mean of all daily or weekly concentrations, of a contaminant measured during a calendar year.
Annual Average Loading	The value obtained by multiplying the <i>Annual Average Concentration</i> of a contaminant by the <i>Average Daily Flow</i> .
Average Daily Flow	The cumulative total sewage flow to the sewage works during a calendar year, divided by the number of days during which sewage was flowing to the sewage works that year.
C of A	Certificate of Approval
CFU	Colony Forming Units
L/s	litres per second
m <sup>3</sup> /d	cubic meters per day
mg/L	milligrams per litre
mL	Milliliter
ML/d	Mega (million) litres per day
MECP	Ministry of the Environment, Conservation and Parks (Ontario)
MOH	Medical Officer of Health
Monthly Average Concentration	The arithmetic mean of all daily or weekly concentrations of a contaminant by the <i>Average Daily Flow</i> over the calendar month.
Monthly Average Loading	The value obtained by multiplying the <i>Monthly Average Concentration</i> of a contaminate by the <i>Average Daily Flow</i> .
O. Reg.	Ontario Regulation



## 1. Introduction

The following 2023 Annual Wastewater Performance Report is submitted in accordance with Condition 8(4) (a) through (i) of the Certificate of Approval (CofA) # 0999-7X8QL3 for the Gananoque Sewage Lagoons. This report has been prepared by the Town of Gananoque's Public Utilities Staff.

## 2. Facility Description

The Gananoque Sewage Lagoons have been in operation for over 50 years. The facility is located north of Highway 401, occupying approximately a 1.5 sq. km (150 ha) parcel of land consisting of 3 Cells.

Raw sewage is received in Cell 1 from the East End Pumping Station (EEPS) through a 400mm diameter forcemain. At the EEPS, alum is added to assist in the reduction of phosphorus and total suspended solids. Once the sewage enters the first cell it flows from one cell to the next allowing the settling of solids and reduction of dissolved nutrients. The final effluent of the Lagoon then discharges to the St Lawrence River.

Refer to "**Appendix A**" to review the systematic drawing.

## 3. Monitoring Raw Influent and Treated Effluent Data

Refer to "**Appendix B**" to review the Summary Performance Report.

### 3.1 Influent and Effluent Lab Results, Limits and Objectives

**Table 1: Raw Influent Results**

Raw Influent Parameter	Annual Average Concentration in mg/l
CBOD <sub>5</sub>	107.58
Total Suspended Solids	171.42
Total Phosphorous	5.68

**Table 2: Effluent CBOD<sub>5</sub> and Total Suspended Solids**

The *Annual Average Concentrations* and *Annual Average Loading* of CBOD<sub>5</sub> and Total Suspended Solids shall not exceed the corresponding average and loading concentrations in the below table.

Effluent Parameter	Annual Average Concentration in mg/l	CofA Concentration Objective in mg/l	CofA Concentration Limit in mg/l	Annual Average Loading in kg/day	CofA Loading Objective in kg/day	CofA Loading Limit in kg/day
CBOD <sub>5</sub>	6.81	25.0	30.0	25.30	133	159
Total Suspended Solids	20.46	25.0	30.0	62.48	133	159

**Table 3: Effluent Total Phosphorous**

The *Monthly Average Concentration* and *Monthly Average Loading* of Total Phosphorous shall not exceed the corresponding average and loading concentrations in the below table.

Effluent Parameter	Monthly Average Concentration in mg/l	CofA Concentration Objective in mg/l	CofA Concentration Limit in mg/l	Annual Average Loading in kg/day	CofA Loading Objective in kg/day	CofA Loading Limit in kg/day
Total Phosphorous	0.43	1.0	1.0	1.53	5.30	5.30

**Table 4: Effluent pH**

The effluent pH must be maintained within the range of 5.5 to 9.5 at all times.

Effluent Parameter	Annual Minimum	CofA Minimum Objective	CofA Minimum Limit	Annual Maximum	CofA Maximum Objective	CofA Maximum Limit
pH	5.7	6.0	5.5	9.6	9.0	9.5

The Lagoon treated effluent pH had an exceedance of 9.6 on May 30<sup>th</sup>, 2023. The pH result of 9.6 was not in conformance with the Certificate of Approvals effluent limits. The Caduceon lab results were received and reviewed on June 13<sup>th</sup>, 2023.

Once reviewed, the pH meter was re-calibrated to ensure it was operating correctly and samples were collected at each cell of the Lagoon and at the treated effluent discharge. The Ministry of the Environment, Conservation and Parks was notified of this event on June 14<sup>th</sup>, 2023.

On June 20<sup>th</sup>, 2023 the Lagoon treated effluent pH was no longer exceeding the effluent pH limit or objective. The below chart displays the pH sample results in response to the exceedance.

Date	Time	Location	Result
June 6, 2023	10:50	Treated Effluent Manhole	9.2
June 13, 2023	09:58	Lagoon Cell 1	7.2
	09:50	Lagoon Cell 2	7.5
	09:44	Lagoon Cell 3	8.9
	09:30	Treated Effluent Manhole	9.2
	11:35	Treated Effluent Manhole	9.3
June 20, 2023	12:23	Treated Effluent Manhole	8.0
June 27, 2023	10:25	Raw Sewage #18 Manhole	7.7
	10:20	Treated Effluent Manhole	7.4
June 28, 2023	15:55	Raw Sewage #18 Manhole	7.7
	14:47	Entering the Lagoon through Cell 1's influent chamber	7.2
	15:02	Leaving the Lagoon's Cell 1 through its effluent chamber	7.4
	15:13	Leaving the Lagoon's Cell 2 through its effluent chamber	7.6
	15:20	Leaving the Lagoon's Cell 3 through its effluent chamber	8.8
	15:50	Treated Effluent Manhole	8.6

**Table 5: Effluent E. Coli**

The E.Coli *Annual Average Geometric Mean Density* shall stay below 200 organisms/100ml. Geometric Mean Density is the nth root of the product of multiplication of the results of n number of samples over the year.

<b>Effluent Parameter</b>	<b>Annual Average (Geometric Mean Density) Count organisms/100ml</b>	<b>Annual Average Geometric Mean Density Objective Count organisms/100ml</b>
E. Coli	80.03	200

### 3.2 Flow Data

The annual average daily treated effluent flow in 2023 was 3,647 m<sup>3</sup> and the annual average daily raw influent flow was 3,276 m<sup>3</sup>. Weather conditions account for variations in flow differentials throughout the year. The table below provides the average monthly raw influent and treated effluent flow.

**Table 6: Average Monthly Flows**

<b>Month</b>	<b>Raw Influent</b>	<b>Treated Effluent</b>
January	119,978	195,445
February	120,472	126,007
March	141,670	144,373
April	124,689	173,191
May	110,519	131,625
June	72,378	64,592
July	76,450	62,682
August	93,973	131,328
September	66,008	66,157
October	67,582	60,251
November	73,104	46,497
December	131,254	131,067

### 3.3 Bypasses and Overflows

There were 2 overflow events during 2023 at the East End Pumping Station and a breach in the berm of Cell 1 at the Lagoon. All events were reported to the Spills Action Centre, the Ministry of Health and a letter was sent to the Ministry of the Environment, Conservation and Parks Inspector.



**Table 7: 2023 Bypass and Overflow Events**

Date	Location	Event	Volume	Duration	Cause
January 4, 2023	East End Pumping Station	Overflow	118 m3	1 Hour 14 Minutes	Heavy Precipitation and Snow Melt
April 30, 2023	East End Pumping Station	Overflow	1579 m3	45 Minutes	Heavy Precipitation and Equipment Failure.

\* The Lagoon berm leak was discovered on January 9th, 2023 during a routine Lagoon inspection. On October 18th, 2023 the repair of the Lagoon berm was complete. Monitoring of Cell 1 continued to ensure flows are operating as expected

#### 4.0 Operating Challenges and Corrective Action

The operation for the Gananoque Lagoon desludging commenced on June 3<sup>rd</sup>, 2020 and was completed on July 7<sup>th</sup>, 2020. The work associated with the dewatered biosolids removal was intermittent between June 6<sup>th</sup> 2023 to September 27<sup>th</sup> 2023.

Refer to “**Appendix C**” for the Bishop Water Biosolids Final Report.

##### 4.1 Maintenance on Major Structures and Equipment

All works are subject to the annual budget process and approval by Council. A 10 Year Capital Equipment Replacement Plan has been developed which includes an extensive breakdown of all capital equipment that requires allocated funds for refurbishment or replacement.

Refer to “**Appendix D**” to review the 2023 capital project highlights.

##### 4.2 Effluent Quality Assurances/ Control Measure

The Corporation of the Town of Gananoque is committed to comply with all applicable legislation and regulatory requirements as it pertains to wastewater effluent quality, environmental protection, and customer satisfaction.

Gananoque continues to achieve these goals through the implementation of a Quality Management System consisting of policies, procedures, and forms. These documents demonstrate risk-based treatment process evaluation, Operating Authority competency, open communications, appropriate contingency/incident response measures and response to consumers’ concerns in a timely manner.



The employees involved within the Wastewater System share responsibilities of implementing, maintaining and contributing to the continual improvement of the Wastewater QMS.

## **5.0 Calibrations/Maintenance of Effluent Monitoring Equipment**

The influent, effluent and pump station flow meters are calibrated annually for accuracy to within plus or minus 10 percent (+/- 10%) of actual flowrate. The last annual calibration was completed on August 31, 2023.

## **6.0 Key Contacts**


David Armstrong  
Manager of Public Works  
Phone: 613-382-2149 ext. 1615  
Fax: 613-342-5035  
Email: pwmanager@gananoque.ca

Don Richards  
Utilities Superintendent  
Phone: 613-382-2149 ext. 1118  
Email: utilitysuperintendent@gananoque.ca

Christine Brennan  
Utilities Compliance Coordinator  
Phone: 613-382-2149 ext. 1612  
Email: utilitycompliance@gananoque.ca



## **Appendix A**



ALL DIMENSIONS AND INFORMATION SHALL BE CHECKED AND VERIFIED ON THE JOB AND ANY DISCREPANCIES MUST BE REPORTED TO THE OWNER THAT BEFORE COMMENCING THE WORK. DIMENSIONS ARE NOT TO SCALE.

THIS DRAWING AND ALL ASPECTS OF IT IS/ARE THE PROPERTY OF THE ENGINEER. NO PART OF THIS DRAWING OR ANY INFORMATION CONTAINED HEREIN MAY BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC, MECHANICAL, OR OTHERWISE, WITHOUT THE EXPRESS WRITTEN PERMISSION OF THE ENGINEER. ANY UNAUTHORIZED REPRODUCTION IS PROHIBITED BY LAW.



884 North Court  
Kingston, Ontario  
K7P 2P9  
TEL: 613-389-3703  
FAX: 613-389-3709  
E-mail: kingston@bh.ca  
www.bh.ca

Chartered Professional Engineer (1997) Licensed

NO.	DATE	BY	REVISION / REVISIONS
1			

CLIENT:

TOWN OF  
GANANOQUE

DRAWN BY:	DESIGNED BY:	CHECKED BY:
GP	SAB	SAB
DATE:	DATE:	DATE:
11/2006	SEPTEMBER 2007	

PROJECT:	PROJECT NO.:
GANANOQUE LAGOON SEWAGE TREATMENT SYSTEM	52-27908
DRAWING:	DRAWING NO.:
DEPTH OF CELL	1







## **Appendix B**



# Summary Performance Report

Month	Days	Flows				Raw			Treated				Performance		
		Raw	Average Raw Day	Treated	Average Treated Day	Raw CBOD5	Raw TSS	Raw TP	Treated CBOD5	Treated TSS	Treated TP	E.Coli (Monthly Geometric Mean)	Removals		
		m3	m3	m3	m3	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	cfu/100mL	%CBOD5	%TSS	%TP
January	31	119,978	3,870	195,445	6,305	107.20	159.40	4.16	6.60	8.00	0.27	305.20	93.84	94.98	93.51
February	28	120,472	4,303	126,007	4,500	95.00	142.50	3.76	10.00	12.25	0.41	3602.64	89.47	91.40	89.10
March	31	141,670	4,570	144,373	4,657	88.75	153.75	2.8	10.25	10.50	0.46	760.53	88.45	93.17	83.57
April	30	124,689	4,156	173,191	5,773	91.25	158.75	4.39	5.25	6.25	0.64	24.30	94.25	96.06	85.42
May	31	110,519	3,565	131,625	4,246	67.00	118.60	3.94	3.20	4.20	0.07	4.80	95.22	96.46	98.22
June	30	72,378	2,413	64,592	2,153	129.75	235.25	18.72	3.00	3.50	0.26	1.32	97.69	98.51	98.61
July	31	76,450	2,466	62,682	2,022	138.50	232.00	6.56	4.00	8.25	0.22	2.51	97.11	96.44	96.65
August	31	93,973	3,031	131,328	4,236	126.20	151.20	4.22	8.40	40.60	0.46	342.80	93.34	73.15	89.10
September	30	66,008	2,200	66,157	2,205	151.25	211.25	6.83	11.50	39.25	0.53	195.21	92.40	81.42	92.24
October	31	67,582	2,180	60,251	1,944	116.8	232.00	5.75	7.20	48.00	0.98	474.84	93.84	79.31	82.96
November	30	73,104	2,358	46,497	1,500	120.3	176.00	5.13	6.75	33.00	0.54	49.66	94.39	81.25	89.47
December	31	131,254	4,234	131,067	4,228	62.25	92.50	3.12	6.00	27.00	0.42	232.50	90.36	70.81	86.54









## **Appendix C**



# BISHOPWATER

16 Edward Street South, Unit 203, Arnprior, ON K7S 3W4  
www.bishopwater.ca info@bishopwater.ca

Phone: 343-361-0463

Fax: 1(844) 272-6102

---

**INTELLIGENT SOLUTIONS FOR WATER**

## **FINAL REPORT**

### **Final Notification of Dewatered Biosolids Removal, Gananoque, ON**

**ECA 1426-8ADGZH  
Section 23.2 (a) "Final Report"**

**2023-10-19**

**Attention:**

***Suzanne Smith***

Water Inspector/Provincial Officer, Badge #1511  
Ministry of the Environment, Conservation and Parks  
Drinking Water and Environmental Compliance Division  
Kingston District Office | P: 613-540-6871 \ C: 613-453-9687 \ F: 613-540-6876  
Email: suzanne.smith@ontario.ca  
CC - Cathy.Chisholm@ontario.ca

**Prepared by:**

Bishop Water Inc.  
Unit 203 - 16 Edward St. S  
Arnprior, Ontario, Canada  
K7S 3W4

## [Table of Contents](#)

<b>1.0 Introduction</b>	<b>2</b>
<b>2.0 Project Timeline</b>	<b>3</b>
<b>3.0 Summary of Dewatered Biosolids Removal Work</b>	<b>3</b>
<b>4.0 Volume/Weight Trucked Off-Site</b>	<b>4</b>
<b>5.0 Photographs</b>	<b>7</b>
<b>6.0 Conclusion</b>	<b>7</b>

## 1.0 Introduction

The following final report has been provided in accordance with Condition 23.2 (a) “ Final report” of ECA 1426-8ADGZH for the sludge removal and sludge dewatering as well as dewatered biosolids removal at the Gananoque Sewage Lagoons.

*Dewatered biosolids were removed from all four (4) 100’ circumference x 86’ length Geotube units at the Gananoque Sewage Lagoons. (44.346623, -76.152075) in Gananoque, ON.*

## 2.0 Project Timeline

Operation for Gananoque lagoon desludging commenced on June 3, 2020 and was completed on July 7, 2020.

Please refer to Table 2 (located below) for a 2020 project timeline.

**Table 1.** Lagoon Sludge Removal & Sludge Dewatering Project Timeline.

<i>Pre-Operation District Office Notification and Pre-Operation Municipal Notification (Section 19.1 and 19.2 ECA 1426-8ADGZH)</i>	April 13 <sup>th</sup> , 2020
<i>Mobilization to Site</i>	May 25 <sup>th</sup> , 2020
<i>Start of desludging operation</i>	June 3 <sup>th</sup> , 2020
<i>End of desludging operation</i>	July 7 <sup>th</sup> , 2020
<i>Demobilization of dredging equipment from Site</i>	July 13 <sup>th</sup> , 2020
<i>MECP Extension Letter #1 (extend Geotube dewatering)</i>	September 2, 2021
<i>MECP Extension Letter #2 (extend Geotube dewatering)</i>	August 3, 2022
<i>MECP Extension Letter #3 (extend Geotube dewatering)</i>	September 7 <sup>th</sup> , 2023

Work associated with the dewatered biosolids removal was intermittent between June 6<sup>th</sup> - September 27<sup>th</sup> 2023. Work commenced with on-site treatment trials on June 6, 2023 and commenced with final removal from Site and demobilization of equipment on September 27, 2023.

Please refer to Table 2 (located below) for a timeline breakdown for the dewatered biosolids removal.

**Table 2.** Dewatered Biosolids Removal Project Timeline.

<i>Pre-Operation District Office Notification and Pre-Operation Municipal Notification (Section 19.1 and 19.2 ECA 1426-8ADGZH)</i>	May 19 <sup>th</sup> , 2023
<i>Trial Phase</i>	June 6 <sup>th</sup> - July 20 <sup>th</sup> , 2023
<i>Full Scale Trucking Phase</i>	August 8 <sup>th</sup> - September 27 <sup>th</sup> , 2023
<i>Demobilization from Site</i>	September 27 <sup>th</sup> , 2023

### 3.0 Summary of Dewatered Biosolids Removal Work

Bishop Water completed a trial (June 6<sup>th</sup> - 13<sup>th</sup>) consisting of ~8 m<sup>3</sup> of dewatered biosolids mixed with monopotassium phosphate fertilizer (MKP) to treat the leachable cadmium. The trial concluded that the MKP treated the leachable cadmium to non-hazardous levels, however the mixing process caused a liquefaction issue.

Bishop Water completed another trial (July 20<sup>th</sup> - 30<sup>th</sup>) with the same ~8 m<sup>3</sup> of dewatered biosolids mixed with monopotassium phosphate fertilizer (MKP) and Metaflo MF006 solidification agent. This both treated the leachable cadmium to non-hazardous level and solved the liquefaction issue (made it so the treated dewatered biosolids passed a slump test after mixing).

Bishop Water mixed the MKP and MF006 with all dewatered biosolids on Site with an excavator. Once each zone went through third-party lab testing to confirm non-hazardous levels of cadmium and a passing slump test the material was trucked off Site to GFL Moose Creek facility for disposal (August 8 - September 27<sup>th</sup>).

### 4.0 Volume/Weight Trucked Off-Site

A total of 94 truckloads for a total of 1493.36 metric tons (MT) was removed from the Site and taken to the GFL facility located at 17335 Allaire Rd - Moose Creek.

Please refer to Table 2 for a full load summary.

**Table 2. Truckload summary.**

Load #	Date	Net Weight	Unit of Measure
1	Sept /8/2023	8.74	MT
2	Sept/11/2023	18.85	MT
3	Sept/11/2023	14.85	MT
4	Sept/11/2023	16.37	MT
5	Sept/11/2023	15.03	MT
6	Sept/11/2023	15.68	MT
7	Sept/11/2023	16.67	MT
8	Sept/11/2023	14.43	MT
9	Sept/11/2023	16.94	MT
10	Sept/11/2023	16.14	MT
11	Sept/11/2023	16.06	MT
12	Sept/11/2023	13.19	MT
13	Sept/12/2023	15.05	MT
14	Sept/12/2023	15.8	MT

15	Sept/12/2023	14.48	MT
16	Sept/12/2023	15.33	MT
17	Sept/12/2023	18.64	MT
18	Sept/12/2023	14.8	MT
19	Sept/12/2023	16.35	MT
20	Sept/12/2023	16.01	MT
21	Sept/12/2023	11.56	MT
22	Sept/12/2023	14.74	MT
23	Sept/12/2023	16.25	MT
24	Sept/12/2023	14.16	MT
25	Sept/13/2023	15.35	MT
26	Sept/13/2023	13.84	MT
27	Sept/13/2023	14.19	MT
28	Sept/13/2023	17.98	MT
29	Sept/13/2023	15.22	MT
30	Sept/13/2023	13.81	MT
31	Sept/13/2023	13.49	MT
32	Sept/13/2023	14.93	MT
33	Sept/13/2023	17.91	MT
34	Sept/13/2023	15.93	MT
35	Sept/13/2023	17.61	MT
36	Sept/13/2023	15.73	MT
37	Sept/13/2023	15.33	MT
38	Sept/13/2023	14.79	MT
39	Sept/14/2023	16.09	MT
40	Sept/14/2023	15.09	MT
41	Sept/14/2023	17.02	MT
42	Sept/14/2023	16.21	MT
43	Sept/14/2023	16.33	MT
44	Sept/14/2023	15.09	MT

45	Sept/14/2023	15.89	MT
46	Sept/14/2023	16.63	MT
47	Sept/14/2023	18.8	MT
48	Sept/14/2023	17.19	MT
49	Sept/14/2023	15.85	MT
50	Sept/14/2023	15.18	MT
51	Sept/15/2023	15.6	MT
52	Sept/15/2023	16.12	MT
53	Sept/15/2023	14.49	MT
54	Sept/15/2023	18.5	MT
55	Sept/15/2023	14.88	MT
56	Sept/15/2023	13.16	MT
57	Sept/15/2023	15.66	MT
58	Sept/15/2023	14.63	MT
59	Sept/15/2023	16.21	MT
60	Sept/15/2023	19.21	MT
61	Sept/15/2023	15.52	MT
62	Sept/15/2023	17.9	MT
63	Sept/15/2023	14.36	MT
64	Sept/15/2023	15.09	MT
65	Sept/15/2023	15.7	MT
66	Sept/15/2023	14.73	MT
67	Sept/20/2023	16.42	MT
68	Sept/20/2023	15.82	MT
69	Sept/20/2023	13.88	MT
70	Sept/20/2023	13.5	MT
71	Sept/20/2023	15.88	MT
72	Sept/20/2023	14.38	MT
73	Sept/20/2023	19.23	MT
74	Sept/20/2023	17.72	MT

75	Sept/20/2023	16.16	MT
76	Sept/20/2023	17.11	MT
77	Sept/20/2023	16.53	MT
78	Sept/20/2023	16.72	MT
79	Sept/20/2023	15.57	MT
80	Sept/20/2023	16.38	MT
81	Sept/20/2023	21	MT
82	Sept/21/2023	16.4	MT
83	Sept/21/2023	14.95	MT
84	Sept/21/2023	16.81	MT
85	Sept/21/2023	14.75	MT
86	Sept/21/2023	18.14	MT
87	Sept/21/2023	19.16	MT
88	Sept/21/2023	14.04	MT
89	Sept/21/2023	15.75	MT
90	Sept/21/2023	14.81	MT
91	Sept/21/2023	9.98	MT
92	Sept/21/2023	16.42	MT
93	Sept/25/2023	26.83	MT
94	Sept/27/2023	19.66	MT
TOTAL		1493.36	



## 5.0 Photographs

Below are key photographs collected during the work.



*Figure 1. Loading truck.*

## 6.0 Conclusion

Bishop Water was able to remove all dewatered biosolids from the site (1493.36 MT total).

Regards,

Breanna Foster  
Project Coordinator  
Bishop Water Inc.



## **Appendix D**

# CARRY FORWARD CAPITAL PROJECTS

**PROJECT NAME:** Water / Wastewater Carry Forward Capital Projects (2020-2021-2022)  
**YEAR:** 2023  
**COST CENTRE:** Capital reserve funded through wastewater revenues  
**LOCATION:** Gananoque Water Treatment Water Distribution Wastewater Collection Wastewater Treatment Lagoon System  
**LENGTH:** On-Going  
**YEAR FIRST INTRODUCED:** 2020  
**PREPARED BY:** D. Richards  
**DATE:** November 10, 2022  
**SCOPE:** Provides for the capital needs for the Gananoque Water / Wastewater Treatment System  
**WHY REQUIRED:** Allows for coordinated planning for equipment upgrades and maintenance requirements  
**BENEFITS:** Ensures that all costs are being captured and financed through the wastewater water rates

PROJECT DESCRIPTION:	NOTES	MGR:	BUDGET:
<b>WASTEWATER TREATMENT EAST END PUMP STATION : BLDG. &amp; PROPERTY MNTCE:</b>			
Force Main Upgrades (2016 Capital Carryover 2-5-08147-5400)	EEPS Force Main Upgrades	DR	113,000.00
Building / Structure (2022 Capital Carryover 2-5-08130-5400 / 2-5-08134-5400)	Chemical Building Structure / Chemical Storage	DR	475,000
Engineering Services (2022 Capital Carryover 2-5-08147-5400)	New Wet Well Forcemain / Chemical Building EEPS	DR	150,000
<b>WASTEWATER TREATMENT LAGOON:</b>			
Lagoon Sludge Removal Cell #1(2021-2022 Carryover 2-5-08105-5400)	Biosolids Disposal	DR	891,000
Lagoon Road & Berm (2022 Carryover 2-5-08124-5400)	Increase Freeboard Cell #1, Vegetation Removal	DR	101,000
<b>WASTEWATER COLLECTION / PUMP STATIONS:</b>			
Pump Station SPS#2 (2022 Carryover 2-5-08210-5400)	Station Shelter	DR	25,000
Stone Street SPS (2022 Carryover 2-5-08146-5400)	Communication Upgrades	DR	40,000
<b>SERVICES / METERING:</b>			
Curb Stop (2020/2021/2022 Capital Carryover 2-508322-5400 / 5318)	Replace Curb Stops	DR	33,140
<b>WATER TREATMENT: BLDG. &amp; PROPERTY MNTCE:</b>			
MCC Electrical Upgrades (2022 Carryover 2-5-08320-5400)	Breaker Replacement	DR	50,000
High Lift Pump #4 (2022 Carryover 2-5-08381-5400)	Refurbishment	DR	105,000
High Lift Pump #4 & #5 (2022 Carryover 2-5-08382-5400)	New VFD	DR	220,000
High Lift Discharge Header (2022 Carryover 2-5-08383-5400)	New Pressure Transducer	DR	20,000
<b>WATERMAINS / HYDRANTS / VALVES</b>			
Leak Detection (2022 Carryover 2-5-08328-5400)	Detection Monitoring Equipment	DR	25,000
Distribution Hydraulic Modeling (2022 Carryover 2-5-08384-5400)	Engineering Services	DR	10,000
Water Tower Communications (2022 Carryover 2-5-08316-5400)	Upgrade Communications	DR	43,000
			<b>2,301,140</b>

# WASTEWATER COLLECTION CAPITAL PROJECTS

**PROJECT NAME:** Wastewater Collection/Construction  
**YEAR:** 2023  
**COST CENTRE:** Capital reserve funded through wastewater revenues  
**LOCATION:** Gananoque Wastewater Collection System  
**LENGTH:** On-Going  
**YEAR FIRST INTRODUCED:** 2020  
**PREPARED BY:** D. Richards  
**DATE:** November 1, 2021  
**SCOPE:** Provides for the capital needs for the Gananoque Wastewater Collection System  
**WHY REQUIRED:** Allows for coordinated planning for equipment upgrades and maintenance  
**BENEFITS:** Ensures that all costs are being captured and financed through the wastewater water rates

PROJECT DESCRIPTION:	NOTES	MGR:	BUDGET:
<b>FULL RECONSTRUCTION PROJECTS (SEWER MAINS &amp; LATERALS)</b>			
Engineering	Arthur Street Reconstruction	BW/DA	325,210
Service Lateral Replacements and Lining / Manhole Refurbishment	On-going program to replace failing sewer laterals and manholes	DR	25,000
<b>WATER STREET PUMP STATION #2:</b>			
<b>MAIN STREET PUMP STATION #3:</b>			
Pump #2 & #3	Pump Refurbishment	DR	60,000
<b>STONE STREET PUMP STATION:</b>			
Controls / Communications	PLC / SCADA Integration Upgrades (Additional Fund Request 2-5-08146-5400)	DR	75,000
			<b>485,210</b>

WASTEWATER TREATMENT CAPITAL PROJECTS	
---------------------------------------	--

<b><u>PROJECT NAME:</u></b>	Wastewater Treatment/Construction
<b><u>YEAR:</u></b>	2023
<b><u>COST CENTRE:</u></b>	Capital reserve funded through wastewater revenues
<b><u>LOCATION:</u></b>	Gananoque Wastewater Treatment Lagoon System
<b><u>LENGTH:</u></b>	On-Going
<b><u>YEAR FIRST INTRODUCED:</u></b>	2020
<b><u>PREPARED BY</u></b>	D. Richards
<b><u>DATE</u></b>	November 1, 2022
<b><u>SCOPE:</u></b>	Provides for the capital needs for the Gananoque Wastewater Treatment System
<b><u>WHY REQUIRED:</u></b>	Allows for coordinated planning for equipment upgrades and maintenance
<b><u>BENEFITS:</u></b>	Ensures that all costs are being captured and financed through the wastewater water rates

[illegible]